



S-3219

FLORENCE UTILITIES WILL REMOVE OVERHEAD SERVICE CONDUCTORS.

METER SOCKET

LOAD SIDE TERMINALS (CUSTOMER TO ATTACH SERVICE ENTRANCE CONDUCTORS TO THIS POINT).

#4 SOLID COPPER TO GROUND ROD.

1" SPACE BETWEEN POLE AND CONDUIT.

CONDUIT ABOVE THIS POINT TO BE FURNISHED & INSTALLED BY FLORENCE UTILITIES

INSTALL AND CAP CONDUIT ABOVE GRADE

#4 SOLID COPPER FROM METER BASE TO GROUND ROD

5/8" X 8 FOOT COPPER GROUND ROD FURNISHED & INSTALLED BY OWNER.

24' MINIMUM

90° SWEEP (36" RADIUS)

90° SWEEP (36" RADIUS)

CUSTOMER TO REMOVE SERVICE MASK AND REPAIR ROOF AND WALLS IF NECESSARY.

CUSTOMER TO FURNISH AND INSTALL UNDERGROUND TYPE METER BASE.

REFER TO LATEST EDITION OF NATIONAL ELECTRICAL CODE (NEC) FOR WIRING REQUIREMENTS BETWEEN METER & MAIN DISCONNECT.

(2) 2 HOLE PIPE STRAPS

CUSTOMER TO FURNISH AND INSTALL 2 1/2" SCHEDULE 40 UL LISTED ELECTRICAL GRADE CONDUIT FROM METER SOCKET TO BASE OF UTILITY POLE OR PAD MOUNTED TRANSFORMER. CONDUIT ROUTE AND INTERMEDIATE PULL BOXES (IF NECESSARY) TO BE DETERMINED BY FLORENCE UTILITIES PERSONNEL.

CUSTOMER TO PAY \$3.00 PER FOOT (MINIMUM \$300.00) TO CONVERT SERVICE FROM OVERHEAD TO UNDERGROUND.

OVERHEAD TO UNDERGROUND CONVERSION